HASSAN DIVISION.

Dated 26th November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 2 P.M., on 21st December 1930, for "Restoring Mavathanahalli Tank, Registered No. 141 of Arsikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money and be superscribed "Tender for Restoring Mavanathanahalli Tank, Registered No. 141 of Arsikere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates should be given both in figures and words.

Abstract estimate for restoring Mavathanahalli Minor Tank, Registered No. 141 of Arsikere Taluk.

Sl. No.	Items of work	Unit	Rate	Quantity	Cost
	Bund R. L. 55·00.		Rs. a. p.		
1	Earthwork to bund with consolidation and lead complete.	C.yds.		6,844	
2	Turfing the slopes	Sq.yd.s		7,119	
3	Removing sand and silt from breach No. 1 ...	C.yds.		218	
4	Cutting steps and grips and scraping grass, etc.	L. S.		...	
5	Earthwork excavating foundation and puddle wall and using to same bund.	C.yds.		78	
6	Puddle clay wall	,,		218	
7	New stone revetment	,,		206	
8	Gravel backing	,,		30	
9	Grade and index stones new	Each		44	
10	Date and register number stone, new ...	,,		1	
11	Bench mark stones, new	,,		2	
12	Clearing jungle with roots	Grade		43	
	Sluice at R. L. 45·00.				
1	Earthwork excavation and refilling with consolidation.	C.yds.		57	
2	Concrete in surki mortar	C.ft.		81	
3	Burnt brick in surki	,,		194	
4	Burnt stone slab 6" dressed and fixed ...	S.ft.		21	
5	Cutting holes in orifice slabs ...	Each		3	
6	Plastering with surki mortar ...	Sqr.		1·71	
7	C. I. pipe 6" dia only fixing and carting charges (pipes supplied departmentally.)	R.ft.		36	
8	Providing plug and rod including locking arrangement complete.	L. S.		...	
	Weir at R. L. 50·00.				
1	Earthwork clearing draft using the same to bund.	C.yds.		298	
2	Rough stone body wall	,,		10	
3	Concrete in surki mortar	C.ft.		135	
4	Surki plastering	Sqr.		4·05	

Notification dated 25th November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 2 P.M., on 21st December 1930, for restoring Alur Chennikere, Arehalli Hobli, Belur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Alur Chennikere, Arehalli Hobli, Belur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates should be given both in figures and words.

Abstract estimate for restoring Alur Chennikere, Arehalli Hobli, Belur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund R. L. 55·00		Rs. a. p.		
1	Clearing jungle and scraping grass on surface of bund.	Grade		7½	
2	Cutting grips on old bund	„		7½	
3	Removing weeds and other acquatic plants from bed of tank to excavate pit for earthwork.	S.yd.		7,410	
4	Cut open the bund for depleting tank and refilling with consolidation.	Lump		sum	
5	Earthwork to bund with consolidation ...	C.yds.		1,990	
6	Turfing slopes	S.yds.		2,083	
7	Providing new grade stones	No.		8	
8	Do index stones	„		8	
9	Do B. M. stones	„		2	
10	Do Register number stones ...	„		1	
	Left Waste Weir.				
1	Earthwork excavating foundation and using the same for right flank.	C.yds.		22	
2	Concrete in surki mortar	C.ft.		36	
3	Burnt brick in surki mortar	„		135	
4	Burnt stone slabs 4" thick dressed ...	S.ft.		85½	
5	Surki plastering	Sqr.		1·229	
6	Rough stone work new	C.yds.		29	
7	Providing 4" dia. C. I. pipes only carting and fixing charges.	R.ft.		13	
8	Earthwork for left flank bund	C.yds.		5	
9	Turfing	Syds.		12	
	Right Waste Weir.				
1	Earthwork excavating foundation and using earth for flank bund.	C.yd.		13	
2	Concrete in surki mortar	C.ft.		63	
3	Burnt brick in in surki	„		152	
4	Burnt stone slabs 4" thick	S.ft.		85½	
5	Surki mortar plastering	Sqr.		1·29	
6	Rough stone work new	C.yds.		32	
7	Providing 4" dia: C. I. pipe	R.ft.		12	
8	Earthwork for finak bund	C.yds.		50	
9	Turfing	S.yds.		74	